




Installation Example
Concrete Class A 15 - D 400

Dynamic shearing forces on pavement / kerb must not affect the channel wall due to the friction connection with the haunching.




as lowered Kerb



as beveled Kerb

- *** 75 - 125 mm as Kerb
- 100 - 125 mm as lowered Kerb
- 75 - 100 mm as beveled Kerb

Category according to EN 1433 / DIN 19580		A 15	B 125	C 250	D 400**	E 600**	F 900**	Applying to following systems: KERBFIX	
Foundation: width x / height y / thickness z (in cm)		15 / * / 15	15 / * / 15	20 / * / 20	20 / * / 20				
EN 206-1 / DIN 1045-2 The named concrete quality is a minimum quality	quality of concrete stretcher	C30/37 XF4,XM1	C30/37 XF4,XM1	C30/37 XF4,XM1	C30/37 XF4,XM1				
	without danger of frost on the lateral support	C 25/30 X0	C 25/30 X0	C 25/30 X0	C 25/30 X0				
	with danger of frost on the lateral support	C25/30 XF3	C25/30 XF3	C25/30 XF3	C25/30 XF3				
The installation examples / advise constantly are adapted to the technical conditions. With new editions older expenditures lose their validity. Before planning or installation please verify the current version at www.hauraton.com In building construction is a sealing layer below the channels necessary. The installation example represents a proven recommendation from HAURATON. The final responsibility for the execution lies with the planner in charge. Specific conditions of the project must be taken into account. ** Installation situations of drainage systems with high dynamic loads (e.g. airports, motorways and manoeuvring areas of buses, lorries and forklifts, etc.) are not sufficiently considered in DIN EN 1433. Please contact us for such applications to work out project-specific solutions.				Date: 28.09.2023		Our general installation instructions apply.		Format DIN A4	 Unit 4, Frenchs Avenue LU6 1BH Dunstable / Bedfordshire United Kingdom Tel. +44 1582 501380 TS-UK@hauraton.com
						scale 1:10			
0000143295_BRITISH.dwg				10		EBBw			
KERBFIX Einbaubeispiel Klasse D 400 in Beton									