


# Installation Example

## Concrete Class A 15 - C 250



\* y = Channel height plus camber

Category according to EN 1433 / DIN 19580		A 15	B 125	C 250	D 400**	E 600**	F 900**	Applying to following systems: <b>RECYFIX PRO 100, 150, 200, 300</b> <b>RECYFIX NC 100, 150, 200, 300</b> <b>SERVICE CHANNEL RECYFIX PRO 200, 300</b>
Foundation: width x / height y / thickness z (in cm)		10 / * / 10	10 / * / 10	10 / * / 15				
EN 206-1 / DIN 1045-2 quality of concrete stretcher		C30/37 XF4, XM1	C30/37 XF4, XM1	C30/37 XF4, XM1				
	The named concrete quality is a minimum quality	without danger of frost on the lateral support	C25/30 X0	C25/30 X0	C25/30 X0			
	with danger of frost on the lateral support	C25/30 XF3	C25/30 XF3	C25/30 XF3				
The installation examples / advise constantly are adapted to the technical conditions. With new editions older expenditures lose their validity. Before planning or installation please verify the current version at <a href="http://www.hauraton.com">www.hauraton.com</a> In building construction is a sealing layer below the channels necessary.					Date: 17.04.2023		Our general installation instructions apply.	
The installation example represents a proven recommendation from HAURATON. The final responsibility for the execution lies with the planner in charge. Specific conditions of the project must be taken into account.					0000039648_BRITISH.dwg		Format DIN A4 scale 1:5	
** Installation situations of drainage systems with high dynamic loads (e.g. airports, motorways and manoeuvring areas of buses, lorries and forklifts, etc.) are not sufficiently considered in DIN EN 1433. Please contact us for such applications to work out project-specific solutions.					12		EBBw	
					RF-PRO-100 Typ 010 Rinnenunterteil Einbaubeispiel Klasse C 250 in Beton		 Unit 4, Frenchs Avenue LU6 1BH Dunstable / Bedfordshire United Kingdom Tel. +44 1582 501380 TS-UK@hauraton.com	